

4-032378

15-065-01593-00-00

7-20

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 3-4-55

SE SW SE /4 SEC. 04 , 09 , 24 W  
330 feet from S section line  
1650 feet from E section line

Operator license# 100

Lease: Keith Well # 3

Operator: Kansas Corporation Commission  
State of Kansas Fee Fund  
Address: 2301 E. 13<sup>th</sup> Street  
Hays, Kansas 67601  
Control #990081-019

County: Graham  
Well total depth 3998 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 215 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Poe Servicing, Inc. License# 3152

Address: Oberlin, Kansas 67749

Company to plug at: Hour: P.M. Day: 20 Month: July Year: 1999

Plugging proposal received from: District #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 9:30 A.M., Day: 20 Month: July, Year: 1999

Actual plugging report: 8 5/8" set at 215' w/N/A sxs. 5 1/2" set at 3996' w/N/A sxs.  
Prod Perfs 3906' - 3910'. Critical area control shots at 1175' and 2125'. Squeezed 5 1/2"  
with 300 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 200#. Close in P.S.I.  
200#. Squeezed 8 5/8" annulus with 50 sxs cement blend to Max. P.S.I. 200#. Close in P.S.I.  
200#. Plug complete.

Remarks: Allied Cement Company

Condition of casing(in hole): GOOD      BAD      Any plug: YES X NO     

Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO     

Plugged through TUBING     , CASING     . Elevation:      GL

I did[ X ] / did not[      ] observe the plugging. *MD*

Carl Goodrow  
(agent)

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
8-11-99  
AUG 11 1999

CONSERVATION DIVISION  
Wichita, Kansas