

4-032377

7-20

15-065-01592-00-000

E-11,613

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 2-18-55

NW SE SE /4 SEC. 04, 09, 24 W
990 feet from S section line
990 feet from E section line

Operator license# 100Lease: Keith Well # 2Operator: Kansas Corporation Commission
State of Kansas Fee FundCounty: GrahamAddress: 2301 E. 13th Street
Hays, Kansas 67601
Control #990081-018Well total depth 4025 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 160 feetAband. oil well___, Gas well___, Input well X, SWD___, D & A___Plugging contractor: Poe Servicing, Inc. License# 3152Address: Oberlin, Kansas 67749Company to plug at: Hour: A.M. Day: 20 Month: July Year: 1999Plugging proposal received from: District #4 StaffCompany: Kansas Corporation Commission Phone: 785-625-0550Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.Plugging Proposal Received by: Carl GoodrowPlugging operations attended by agent? All[X], Part[], None[]Completed: Hour: 10:45 A.M., Day: 20 Month: July, Year: 1999

Actual plugging report: 8 5/8" set at 229' w/160 sxs cwc. 5 1/2" set at 4024' w/150 sxs.
Prod Perfs 3930' - 3936'. Critical area control shots at 1225' and 2140'. Squeezed 5 1/2"
with 300 sxs cement blend with 500# hulls to Max. P.S.I. 800#. Close in P.S.I. 300#.
Squeezed 8 5/8" annulus with 50 sxs cement blend to Max. P.S.I. 100#. Close in P.S.I. 100#.
Plug complete.

Remarks: Allied Cement Company

Condition of casing(in hole): GOOD___ BAD___ Anhy.plug: YES X NO___
Bottom plug(in place): YES___, CALC___, NO___ Dakota plug: YES X, NO___
Plugged through TUBING___, CASING___ Elevation:___ GL

I did[X] / did not[] observe the plugging.Carl Goodrow
(agent)

RECEIVED
STATE CORPORATION COMMISSION
8-11-99
AUG 11 1999

Form CP-2/3

CONSERVATION DIVISION
Wichita, Kansas