

4-032375

AP 15-065-01590-00-01

E-11,613.7

7-20

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 9-12-55

SE SW NE /4 SEC. 04, 09, 24 W
2970 feet from S section line
1650 feet from E section line

Operator license# 100Lease: Hildebrand Well # 3

Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990081-010

County: Graham
Well total depth 4030 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 226 feet

Aband. oil well___, Gas well___, Input well X, SWD___, D & A___Plugging contractor: Poe Servicing, Inc. License# 3152Address: Oberlin, Kansas 67749Company to plug at: Hour: A.M. Day: 20 Month: July Year: 1999Plugging proposal received from: District #4 StaffCompany: Kansas Corporation Commission Phone: 785-625-0550Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:45 A.M., Day: 20 Month: July, Year: 1999

Actual plugging report: 8 5/8" set at 226' w/160 sxs cwc. 5 1/2" set at 4029' w/75 sxs.
TOC est. at 3529' with annulus to surface with bentonite mud. Prod Perfs 3962' - 3966'.
Critical area control shots at 1250' and 2180'. Squeezed 5 1/2" with 350 sxs cement blend with
450# hulls mixed in to Max. P.S.I. 100#. Close in P.S.I. 0#. Squeezed 8 5/8" annulus with
50 sxs cement blend with 50# hulls mixed in to Max. P.S.I. 100#. Close in P.S.I. 100#. Plug
complete.

Remarks: Allied Cement Company
Condition of casing(in hole): GOOD___ BAD___ Anhy.plug: YES X NO___
Bottom plug(in place): YES___, CALC___, NO___ Dakota plug: YES X, NO___
Plugged through TUBING___, CASING___ Elevation:___ GL

I did[X] / did not[] observe the plugging.

Carl Goodrow
(agent)

RECEIVED
STATE CORPORATION COMMISSION
8-11-99
AUG 11 1999

CONSERVATION DIVISION
Wichita Kansas

Form GR-2/3

(P)