

15-065-20417-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2-4-74
FPM 4 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Hess of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Hess guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Butcher Well No. B-2

Location: W/2-NE-SE Sec. 32 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 4035' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hess was instructed to plug the well as follows:

191'--8 5/8" Surface casing, cement circulated with 150 Sx.
4029'--4 3/8" Production casing cemented on bottom with 175 Sx. No plug-
back indicated. Top perforations from 3954' to 3957'.

Push plug to 3850', sand back to 3800' and set 4 Sx. cement with dump
bailer. Pull 4 3/8" casing and squeeze with 5 sacks hulls, 25 sacks gel
and 150 Cu. Ft. cement, staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent