

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 4 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Joe Hess of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Hess guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Butcher Well No. B-1

Location: SW-NW-SE Sec. 32 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 4030' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Hess was instructed to plug the well as follows:

192'--8 5/8" Surface casing, cement circulated with 175 Sx.  
4029'--4 1/2" Production casing cemented on bottom with 175 Sx. No plug-back indicated. Top of cement @ 3300'. Top perforations from 3953' to 3958'.

Push plug to 3850', sand back to 3800' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

*H. L. Nichols*  
Conservation Division Agent