

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 11-1-67
 NOV 1 1967

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

CONSERVATION DIVISION
 WICHITA, KANSAS

Dear Sir:

Mr. Duane Born of Paine Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Et al, Incorporated,

Complete Address: 501 Cameron Building, Oklahoma City, Oklahoma.

Lease Name: Rice Well No. 1

Location: SW-SE-SW Sec. 33 Twp. 9 Rge. (E)(W) 23

County Graham Total Depth 3797 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Born was instructed to plug the well as follows:

226'--7" OD Surface casing, cement circulated with 125 Sx. (6 1/4" hole).
 Dakota section from 1200' to 1000'.

Circulate hole with heavy mud. Pull DP to 1220' and displace 55 Sx.
 cement thru DP. Pull DP to 210' and displace 15 Sx. cement thru DP.
 Pull DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
 Conservation Division Agent