



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
7-26-71
JUL 26 1971
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ed. Weiler of Shields Drilling Company, Inc has this date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Incorporated,

Complete Address: Shields Building, Russell, Kansas.

Lease Name: Rice Estate Well No. 1

Location: W/2-SW-SW Sec. 33 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 4036' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Weiler was instructed to plug the well as follows:

252'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 925'.

Circulate hole with heavy mud. Pull DP to 1150' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

N. L. Dickow
Conservation Division Agent