



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
7-8-71
JUL 8 - 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ed. Weiler of Shields Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Black Petroleum, Incorporated,

Complete Address: 445 O.W. Garvey Bldg., Wichita, Kansas.

Lease Name: Law Well No. 1

Location: SW-NE-SW Sec. 34 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3975' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weiler was instructed to plug the well as follows:

208'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 825'.

Circulate hole with heavy mud. Pull DP to 1050' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

K. L. Dehler
Conservation Division Agent