

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

RECEIVED STATE CORPORATION COMMISSION 10-21-74 OCT 21 1974

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Sam Waggoner of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Waggoner guarantees payment of the plugging fee.

Operator's full Name: Barnett Oil, Incorporated,

Complete Address: 411 First National Bank Bldg., Wichita, Kansas.

Lease Name: Schweitzer Well No. 1

Location: NE-SE-SE Sec. 35 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 397 1/2' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Waggoner was instructed to plug the well as follows:

16 RT 230'--8 5/8" Surface casing, cement circulated with 150 Sx. Top of Dakota section @ 875'.

Circulate hole with heavy mud. Pull DP to 1100' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

R. L. Nichols Conservation Division Agent