



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 6 1963
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Earl Dunlap of C & G Drilling Co. has this

date requested permission to plug the following described well:

D. G. Hansen

Mr. Dunlap guarantees payment of the plugging fee.

Operator's full Name: D. G. Hansen

Complete Address: Box #195, Logan, Kansas.

Lease Name: Rice Well No. 4

Location: SW-NW-NW Sec. 35 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3980 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dunlap was instructed to plug the well as follows:

198'--8 5/8" surface pipe, cement circulated.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx cement.

" " 190' and 20 Sx cement.

" " 40' and 10 Sx cement
 with 1/2 Sk hulls.

Very truly yours,

H. L. Nichols
 Conservation Division Agent