

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1973
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Del Doherty of Champlin Petroleum Company has this
date requested permission to plug the following described well:Mr. Doherty guarantees payment of the plugging fee.Operator's full Name: Champlin Petroleum Company,Complete Address: 2915 North Lincoln, Oklahoma City, Oklahoma.Lease Name: Clara F. Rice Well No. 1Location: SW-SW-NW Sec. 35 Twp. 9 Rge. (E)(W) 23County: Graham Total Depth 4000' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Doherty was instructed to plug the well as follows:

191'--8 5/8" Surface casing, cement circulated with 135 Sx.
3998'--5 1/2" Production casing cemented on bottom with 200 Sx. Well plugged
back to 3967'. Top of perforations @ 3734'. 5 1/2" has been squeezed w/150
Sx. cement in the Cedar Hills with top of cement @ 1045'.

Squeeze 5 1/2" with 1 sack hulls 33 sacks gel and 100 Sx. cement, staged.
Try to pump in to annulus, if possible squeeze with 1 sack hulls, 10
sacks gel and 60 Sx. cement, staged.

Very truly yours,

N. L. Nichols
 Conservation Division Agent