

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
8-20-65
AUG 20 1965

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Norman Brungardt of Barnes & Sons Pipe Pulling ~~is~~ this

date requested permission to plug the following described well:
Fender Pipe & Sup.

Mr. Brungardt guarantees payment of the plugging fee.Operator's full Name: Fender Pipe and Supply, Incorporated,Complete Address: Box #302, Russell, Kansas.Lease Name: Hildebrand Well No. 1Location: C/N?2-NW-SW Sec. 4 Twp. 9 Rge. (E)(W) 24County Graham Total Depth 4050 Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. was instructed to plug the well as follows:

235'--8 5/8" Surface pipe, cement circulated.
4048'--5 1/2" Production casing cemented?? (Number of Sx. not designated).
Well plugged back to 4013. Top perforations from 3979 to 3984.

Sand well back to 3970' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" to 600' and circulate heavy gel mud. Pull 5 1/2" to 540'
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 220' and dis-
place 20 Sx. cement thru 5 1/2". Pull 5 1/2", set rock bridge @ 35'
and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. D. Nichols
Conservation Division Agent