

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-24,728-00-00

LEASE NAME Bowlby

WELL NUMBER #3

3630' Ft. from S Section Line

4950' Ft. from E Section Line

SEC. 23 TWP. 11 RGE. 16 (E) or (W)

COUNTY Ellis

Date Well Completed 2-16-91

Plugging Commenced 2-16-91

Plugging Completed 2-16-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR D-Oil Co.

ADDRESS Box 278, Victoria, Kansas 67671

PHONE# (913) 735-9225 OPERATORS LICENSE NO. 9394

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 13, 1991 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface Pipe	0	207'	8 5/8	5 jts.	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugs: 990' 25sks, 540' 100sks 1 flow seal, 250' 40sks, 40' 10sks. rat hole 15sks. Total 190sks, 60/40poz, 6% gel, 3% cc, 1sk flow seal, plug down @ 11:00 P.M. 2-16-91.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Western Kansas Drilling, Inc. License No. 4083

Address 117 E. 13th St., P.O. Box 126, Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: D-Oil Co.

STATE OF Kansas COUNTY OF Ellis, ss.


Allen P. Dreiling (Employee of Operator) (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) _____

(Address) P.O. Box 278 Victoria 67671

SUBSCRIBED AND SWORN TO before me this 15 day of March, 19 91

My Commission Expires: _____



Notary Public

DRILLER'S LOG

Operator: D-Oil Co.

Contractor: Western Kansas Drilling, Inc.

Well & Well Description: Bowlby #3
NE-SW-NW 23-11-16 Ellis County, Kansas

Commenced: 2-9-91

Completed: 2-16-91

Character of Well: D & A

Elevation: 1819' GL 1824' KB

Casing: Ran 5 jts. of 8 5/8's set @ 207'


Figures Indicate Bottom of Formations

0' - 982'	Sand & Shale
982' - 1018'	Anhy.
1018' - 1570'	Sand & Shale
1570' - 2165'	Shale
2165' - 3390'	Lime & Shale

STATE GEOLOGICAL SURVEY
MAR - 4
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas)
County of Ellis) ss:

I Stanley Younger, President of Western Kansas Drilling, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the Bowlby #3


Stanley Younger, President