

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: ARES Energy, Ltd.
Address: 303 West Wall Street, Suite 900, Midland, Texas 79701
Phone: (432) 685-1960 Operator License #: 33770
Type of Well: O/G KCC PKT PER CP 2/3 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7-20-08 (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Morrow Depth to Top: 5348' Bottom: 5358' T.D. 5412'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-033-20871-0001
Lease Name: Bluff Creek
Well Number: 5-15 OWWO
Spot Location (QQQQ): _____ - NW - SW - SE
1,100 Feet from North / South Section Line
2,500 Feet from East / West Section Line
Sec. 5 Twp. 34 S. R. 20 East West
County: Comanche
Date Well Completed: 11-15-07
Plugging Commenced: 7-21-08
Plugging Completed: 7-23-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
5124' - 5150' Cherokee	Water	Surf	60'	20"	60'	0'
5238' - 5358' Morrow	Water	Surf	675'	8 5/8"	675'	0'
5362' - 5412' Mississippian	Water	2934'	5412'	5 1/2"	5412'	2934'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 5293' & dumped 2 sxs cement on top. Free pointed and cut off 4 1/2" casing @ 2934'. Circulated hole w/ gelled water. Pulled casing to 700'. Spotted 60 sxs 60/40 Poz + 4% gel plug from 700' - 550' thru casing. Pulled casing to 360'. Spotted 40 sx 60/40 Poz + 4% gel plug from 360' - 200'. Pulled casing to 40' & spotted 25 sx 60/40 Poz + 4% gel plug to surface


Name of Plugging Contractor: Best Well Service Inc License #: N/A
Address: P. O. Box 848, Shattuck, OK., 73853

Name of Party Responsible for Plugging Fees: ARES Energy, Ltd.
State of Texas County, Midland, ss.

Brian P. Ramey, Operations Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Brian P Ramey
(Address) 303 West Wall Street, Suite 900, Midland, Texas 79701

SUBSCRIBED and SWORN TO before me this 5th day of December, 20 08
Lori A. Ellis My Commission Expires: 12-02-2010
Notary Public



PT