

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: McElvain Oil & Gas Properties, Inc.
Address: 1050 17th Street, Suit 1800 Denver, Co. 80265-1801
Phone: (303) 893-0933 X379 Operator License #: 9810
Type of Well: DH KCCPKTPEL CP2/3 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11/12/08 (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-163-23753-00-00
Lease Name: Duncan
Well Number: #1-32
Spot Location (QQQQ): SW - NE - SW - NW
1887 Feet from North / South Section Line
676 Feet from East / West Section Line
Sec. 32 Twp. 6 S. R. 17 East West
County: Rooks
Date Well Completed: NA
Plugging Commenced: 11/12/08
Plugging Completed: 11/12/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Dakota	Water	321'	394'	8-5/8", 24#, J-55	Landed at 1,047'	0'
Cedar Hills	Water	800'	997'			
Anhydrite		1,301'	1,333'			
Lansing		3,032'	3,262'			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Cement plugs were displaced with water while laying down 4-1/2" drill pipe as follows: Plug #1: 25 sx Common from 3,327' to ~3,240'.

Plug #2: 25 sx Common from 1,325' to ~1,148'. Plug #3: 40sx Common from 1,100' to ~950'.


Plug #4: 50 sx Common from 750' to ~585'. Plug #5: 10 sx Common from 40' to surface. 30 sx spotted in rat hole.

Note: tops of cement plugs are calculated

Name of Plugging Contractor: American Eagle Drilling LLC License #: 20-59758
Address: P.O. Box 31 Russell, Kansas 67665

Name of Party Responsible for Plugging Fees: McElvain Oil & Gas Properties, Inc.
State of Colorado County, Denver, ss. **RECEIVED CONSERVATION DIVISION WICHITA, KS**

James Marshall McKinney, Jr. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath says that I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) J.M. McKinney
(Address) 1050 17th Street, Suit 1800 Denver, Co. 80265-1801

SUBSCRIBED and SWORN TO before me this 2 day of December, 2008

Deborah K Powell My Commission Expires: _____
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials