


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 23 Twp. 9S Rge. 24W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW

Lease Owner Leben Drilling, Inc. Etal

Lease Name Nickelson

Well No. A-#1

Office Address Box 486, Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-20-66 19

Application for plugging filed 1-20-66 19

Application for plugging approved 1-20-66 19

Plugging commenced 1-20-66 19

Plugging completed 1-20-66 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4060 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	216'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set Plug @ 540' with 20 sacks cement
Set Plug @ 210' with 20 sacks cement
Bridged Plug @ 40' with 1/2 sack hulls, 10 sacks cement

1-25-66

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January, 19 66

My commission expires April 1, 1967

Ulanda Nichols
Notary Public.

DRILLER'S LOG

COMPANY: Leben Drilling, Inc. Etal
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: NICKELSON A-#1
 LOCATION: SE SE SW Sec. 23-9S-24W
 GRAHAM COUNTY, KANSAS
 COMMENCED: 1-9-66
 COMPLETED: 1-20-66

0	105	Surface Clay, Sand
105	1190	Shale
1190	1250	Sand, Shale
1250	1450	Shale, Sand
1450	1970	Shale, Redbed
1970	2111	Shale
2111	2151	Anhydrite
2151	2480	Shale, Shells
2480	3595	Lime, Shale
3595	3733	Lime
3733	3805	Lime, Shale
3805	4022	Lime
4022	4060	Lime, Shale
	<u>4060</u>	<u>RTD - D. & A.</u>

[Handwritten notes and stamps, including "23 9S 24W"]

Set 8 5/8" used surface casing @ 216' with 150 sks. Common 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Nickelson A-#1 well, located SE SE SW of Section 23, Township 9 South, Range 24 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 24th day of January, 1966.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
 April 1, 1967