


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 23 Twp. 9 Rge. 24 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE NW SW
Lease Owner Don E. Pratt Oil Operations
Lease Name Nickelson 'A' Well No. 4
Office Address P.O. Box 370, Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed August 1 19 66
Application for plugging filed August 1 19 66
Application for plugging approved August 1 19 66
Plugging commenced August 1 19 66
Plugging completed August 1 19 66
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4060 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|--------------|---------|------|----|--------|--------|------------|
| Surface Pipe | | | | 8-5/8" | 204' | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rotary mud to a depth of 540' where first plug was set using 20 sacks of cement. Filled hole with rotary mud to a depth of 200' where second plug was set using 20 sacks of cement. Rotary mud was used to fill hole to depth of 40' where third plug was set using 10 sacks of cement and filled to surface.

8-5-66
RECEIVED
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Victoria, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Leo F. Dreiling (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
Leo F. Dreiling, Victoria, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of August, 1966

My commission expires May 14, 1968

Joseph A. Hess
Joseph A. Hess Notary Public.

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

| | | | | |
|-------------|---|---------------|-----------|--|
| Company | Don E. Pratt Oil Operations Hays, Kansas | Sec. 23 | Twp. 9 | Rng. 24 |
| Farm | Nickelson A No. 4 | Location | SE | NW SW |
| Total Depth | 4060' | County | Graham | |
| Comm. | 7-26-66 | Comp. | 8-1-66 | Elevation: |
| Contractor | L. J. Dreiling & Sons, Inc. Victoria, Kansas | | | K.B. 2486' D.F. 2483' G.R. 2481' |
| | Casing Record 204' of 8 5/8" | Cement Record | 150 sacks | |
| | | Production: | D & A | |

Figures Indicate Bottom of Formations

| | | |
|-------|--------|-----------------|
| 0' | 130' | Clay and Sand |
| 130' | 204' | Shale |
| 204' | 685' | Shale |
| 685' | 1680' | Shale |
| 1680' | 1876' | Sand |
| 1876' | 1900' | Red Bed & Shale |
| 1900' | 2125' | Red Bed & Shale |
| 2125' | 2161' | Anhy. |
| 2161' | 2505' | Shale & Shells |
| 2505' | 2830' | Shale & Lime |
| 2830' | 3050' | Shale & Lime |
| 3050' | 3335' | Lime & Shale |
| 3335' | 3550' | Shale & Lime |
| 3550' | 3750' | Lime & Shale |
| 3750' | 3855' | Lime & Shale |
| 3855' | 3898' | Lime |
| 3898' | 3916' | Lime |
| 3916' | 3922 | Lime |
| 3922' | 4000' | Lime |
| 4000' | 4040' | Lime |
| 4040' | 4060' | Lime |
| 4060' | R.T.D. | |

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Nickelson A #4.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 3rd day of August 1966.

Joseph A. Hess

NOTARY PUBLIC

My commission expires: May 14, 1966

RECORDED
INDEXED
AUG 5 1966