

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 23 Twp. 9 Rge. 24 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SE NE SW

Lease Owner Leo J. Dreiling Oil Company

Lease Name Nickelson Well No. 8

Office Address Route 2, Victoria, Kansas 67671

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-9 1970

Application for plugging filed 3-9 1970

Application for plugging approved 3-9 1970


Plugging commenced 3-9 1970

Plugging completed 3-9 1970

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	209'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st. plug was set @ 1200' with 70 sacks cement

2nd. plug was set @ 210' with 20 sacks cement

3rd. plug was set @ 40' with 10 sacks cement

Cementing to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
3-12-70 MAR 12 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.

Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF KANSAS, ss.

I, Leo F. Dreiling (employee of owner) or (~~owner or contractor~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling


LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671

(Address)

SUBSCRIBED AND SWORN to before me this 10th day of March, 19 70

My commission expires September 19, 1970

Joseph A. Hess
JOSEPH A. HESS Notary Public.



L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

WELL LOG

Company	Leo J. Dreiling Oil Company Route 2 Victoria, Kansas 67671	Sec. 23	Twp. 9	Rng. 24
Farm	Nickelson No. 8	Location	SE NE SW	
Total Depth	4050'	County	Graham	
Comm.	3-2-70	Comp.	369-70	Elevation: 2463' K. B.
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas 67671			2460' D. F.
	Casing Record	Cement Record		2458' G. R.
	209' - 8 5/8"	160 sacks cement		Production: D & A

Figures Indicate Bottom of Formations

0'	163'	Post Rock & Sand
163'	600'	Shale
600'	2098'	Shale & Sand
2098'	2137'	Anhy.
2137'	2715'	Shale
2715'	3860'	Shale & Lime
3860'	4050'	Lime
4050'	T.D.	

RECEIVED
STATE CORPORATION COMMISSION
MAP 12 1970
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Nickelson #8.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 9th day of March 1970.

Joseph A. Hess

JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970

