


15-065-00689-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 29 Twp. 9 Rge. 24 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW/4 SW/4 NW/4
Lease Owner Empire Drilling Co.
Lease Name Empire Drilling Co-Nicholson Well No. 1
Office Address Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 6-14-55 19
Application for plugging filed 3-19-56 19
Application for plugging approved 3-21-56 19
Plugging commenced 4-14-56 19
Plugging completed 4-25-56 19
Reason for abandonment of well or producing formation Went to water

If a producing well is abandoned, date of last production 3-16-56 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty 4015 RT KCC
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3950 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	172'	None
				5 1/2"	4015'	2,863'9"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3950 feet to surface feet for each plug set.

Well had been previously plugged back from bottom of hole to 3950 ft with cement; Hole filled with sand from 3950 to 3800 ft; Four sacks of cement placed in hole with dump bailer to form cement plug from 3800 to 3768 ft; Hole filled with mud from 3768 to 180 ft; Ten foot rock bridge installed between 180 ft and 170 feet; Fifteen sacks of cement poured in hole and hole mudded to 35 ft. Ten foot rock bridge installed between 35 and 25 ft; Hole capped with ten sacks of cement

5-12-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pipe Pulling Co
Address Russell, Kansas.


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
DAN J. KORNFELD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
DAN J. KORNFELD, Operator
400 Brown Building, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May, 19 56

My commission expires Oct. 21, 1958

Lucille Harr
Lucille Harr Notary Public.



L O G

COMPANY: EMPIRE DRILLING COMPANY
 CONTRACTOR: EMPIRE DRILLING COMPANY
 FARM: E. R. NICKELSON #1
 LOCATION: SW SW NW, SEC. 23-9-24
 GRAHAM COUNTY, KANSAS
 COMMENCED: JUNE 3, 1955
 COMPLETED: JUNE 14, 1955

0	TO	190	SURFACE
190	TO	2090	SHALE AND SHELLS
2090	TO	2130	ANHYDRITE
2130	TO	2791	SHALE AND SHELLS
2791	TO	3770	LIME AND SHALE
3770	TO	3960	LIME
3960	TO	4015	LIME AND SHALE
4015			R.T.D.

SET 8 5/8" SURFACE CASING AT 172' CEMENTED WITH 115 SACKS CEMENT.

ELEVATION: 2447 K.B.

TOPS: ANHYDRITE 2090'; HEEBNER 3763'; TORONTO 3787'; LANSING 3800'; R.T.D. 4015'.

D.S.T. #1 3945 TO 3960'; D.S.T. #2 3962'; D.S.T. #3 3982 TO 4015'.

RAN 51" CASING SET @ 4014' CEMENTED WITH 50 SACKS CEMENT.

C E R T I F I C A T I O N

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE #1 E. R. NICKELSON, SW SW NW, SECTION 23, TOWNSHIP 9 SOUTH, RANGE 24 WEST, GRAHAM COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld
 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 2ND DAY OF MAY, 1956.

MY COMMISSION EXPIRES Oct 21, 1958

Lucille Horn
 NOTARY PUBLIC

PLUGGING
 FILE SEC. 23 9 24W
 BOOK PAGE 47 LINE 12