

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 23 TWP. T9S RGE. R24W E/W
Location as in quarters or footage from lines:
N/2 NE NE

Lease Owner Reach Petroleum Corporation
Lease Name #1 Nickelson Well No. #1
Office Address 3751 East Douglas, Wichita, Kansas 67218
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole
Date Well Completed 2-21-82
Application for plugging filed 2-21-82
Plugging commenced 2-21-82
Plugging completed 2-21-82

Locate Well
correctly on above
Section Platt.

Reason for abandonment of well or producing formation no commercial quantity of oil or gas, encountered
Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well 7
Producing formation Depth to top bottom T.D. 4645²¹⁴

Show depth and thickness of all water, oil and gas formations.

RT
KCC

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged with 70 sx at 1230'
40 sx at 250'
10 sx at 40'
10 sx rathole
5 sx mousehole

50-50 % pass
4% Gel 3% cc.

RECEIVED
STATE CORPORATION COMMISSION
3-12-82
MAR 12 1982
CONSERVATION DIVISION
WICHITA, KANSAS


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton, P.O. Box 1431, Duncan, Oklahoma 73536

STATE OF Kansas COUNTY OF Sedgwick, ss.
Floyd C. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Floyd C. Wilson
3751 E. Douglas, Wichita, Ks
(Address) 67218

SUBSCRIBED AND SWORN TO before me this 26th day of February, 19 82

My Commission expires: April 20, 1983

Linda Joyce Overman
Notary Public.



REACH DRILLING CORPORATION

March 5, 1982

RE: RPC #1 Nickelson
N/2 NE NE
Sec. 23-T9S-R24W
Graham Co., Ks.

OPERATOR: Reach Petroleum Corporation

CONTRACTOR: Reach Drilling Corporation

DRILLING DATES: February 13th, thru February 21st, 1982

Surface pipe 259' w/200 sx common 3% cc & 2% Gel

0	289	Sand
289	1197	Shale
1197	2090	Shale to Sand
2090	2109	Anhy.
2109	2127	Anhy.
2127	2470	Shale
2470	2630	Shale
2630	2970	Shale
2970	3225	Shale to Lime
3225	3345	Shale to Lime
3345	3543	Lime to Shale
3543	3730	Lime to Shale
3730	3852	Shale to Lime
3852	3870	Lime
3870	3896	Shale to Lime
3896	3916	Lime to Shale
3916	3955	Lime
3955	4030	Lime to Shale
4030	4089	Shale to Lime
4089	4182	Lime to Shale
4182	4210	Lime

We certify that the above and foregoing is a true and correct copy of the log on the Reach Petroleum Corporation #1 Nickelson, in Graham County, Kansas.

REACH DRILLING CORPORATION

Floyd C. Wilson

Floyd C. Wilson
President

Subscribed and sworn to before me this 5th day of March, 1982.

Linda J. Overman

Notary Public