

LEASE NAME DRURY 'B'

WELL NUMBER #1

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 24 TWP. 09 RGE. 24 (E) or (W)

COUNTY GRAHAM

Date Well Completed 01/1960

Plugging Commenced 11/29/93

Plugging Completed 11/29/93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR WOODMAN-IANNITTI OIL COMPANY

ADDRESS PO BOX 308; GREAT BEND KS 67530-0308

PHONE# (316) 792-2921 OPERATORS LICENSE NO. 6588

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 22, 1993 (date)

by Dennis Hame1 (KCC District Agent's Name).

Is ACO-1 filed? N/A 1960 If not, is well log attached? no, Sent w/CP-1

Producing Formation KS. CITY Depth to Top 3758' Bottom 3971' T.D. 3980'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	149'	8-5/8"	149'	none
		0	3971'	5-1/2"	3971'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
 Perfed @ 950' & 2075', 3 holes each on 11/29/93. Cemented w/ a total of
 275 sax 60-40 Poz + 10% gel, 1/4# F.C as follows: 50 sax cement & 2 sax hulls down 5-1/2" csg
 followed by 10 sax gel, and 175 sax cement w/200# hulls. Max 1000# SIP 800#. Pumped 50 sax
 cement down 8-5/8" w/100# hulls. Max 1000#, SIP 800# Job completed 1:40 PM.

Name of Plugging Contractor ALLIED CEMENTING CO., INC. License No. _____

Address PO BOX 31; RUSSELL KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WOODMAN-IANNITTI OIL COMPANY


STATE OF KANSAS COUNTY OF BARTON, ss.

D. J. Iannitti, Partner (Employer or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) D. J. Iannitti

(Address) WOODMAN-IANNITTI OIL COMPANY
 PO BOX 308; GREAT BEND KS 67530

SUBSCRIBED AND SWORN TO before me this 29th day of DECEMBER, 19 93



Sharon K. Lingreen
 Notary Public
 My Commission Expires: May 12, 1996 SHARON K. LINGREEN

USE ONLY ONE SIDE OF EACH FORM