

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

K.A.R.-82-3-117

15-005-01618-0000
API NUMBER 15/NA 6/16/60

LEASE NAME DRURY 'B'

WELL NUMBER #2

1320 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 24 TWP. 09 RGE. 24 (X) or (W)

COUNTY GRAHAM

Date Well Completed 8/1960

Plugging Commenced 11/29/93

Plugging Completed 11/29/93

LEASE OPERATOR WOODMAN-IANNITTI OIL COMPANY

ADDRESS PO BOX 308; GREAT BEND KS 67530

PHONE# (316) 792-2921 OPERATORS LICENSE NO. 6588

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 22, 1993 (date)

by DENNIS HAMEL (KCC District Agent's Name).

Is ACO-1 filed? N/A 1960 if not, is well log attached? No/Sent w/CP-1

Producing Formation KS City Depth to Top 3766' Bottom 3975' T.D. 3985'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	152'	8-5/8"	152'	none
		0	3975'	5-1/2"	3975'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set
Perfed @ 950' & 2075' 3 holes each, 11/29/93. Cemented w/a total of 275 sax 60-40 Poz + 10% gel & 1/4# F.C. as follows: 50 sax cement & 2 sax hulls down 5-1/2" casing, followed by 175 sax cement w/ 2 sax hulls and 10 sax gel. Max 1000#, SIP 800#. Pumped in 50 sax cement w/ 1 sax hulls down 8-5/8" Max 1000# SIP 800# Job complete @ 12:15 PM

Name of Plugging Contractor ALLIED CEMENTING CO., INC. License No.

Address PO BOX 31; RUSSELL KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WOODMAN-IANNITTI OIL COMPANY


STATE OF KANSAS COUNTY OF BARTON, SS.

D. J. IANNITTI PARTNER

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) *D. J. Iannitti*

(Address) WOODMAN-IANNITTI OIL COMPANY
PO BOX 308; GREAT BEND KS 67530



SUBSCRIBED AND SWORN TO before me this 29th day of DECEMBER, 1993

Sharon K. Lingreen
Notary Public

MAY 12, 1996 SHARON K. LINGREEN

USE ONLY ONE SIDE OF EACH FORM

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1993
12-30-93

CONSERVATION DIVISION
Wichita, Kansas