


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 24 Twp. 9 Rge. (E) 24 (W)
Location as "NE/CNWxSWx" or footage from lines. SE SE SE 1/4
Lease Owner H-30, Inc
Lease Name Nickelson Well No. 1
Office Address 709 Petroleum Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed Mar 30 19 58
Application for plugging filed Mar 30 19 58
Application for plugging approved Mar 30 19 58
Plugging commenced Mar 30 19 58
Plugging completed Mar 30 19 58
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	197	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole with heavy rotary mud to 500 ft.,
set plug and cemented with 25 sacks cement
through drill pipe. Mudded hole to 190 ft, set plug
run 1/2 sack hulls and cemented with 15 sacks cement
through drill pipe. Mudded hole to 40 ft, set plug,
run 1/2 sack hulls and cemented with 10 sacks
cement to bottom of cellar.

4-5-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.
Address 709 Petroleum Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address) _____

SUBSCRIBED AND SWORN TO before me this 4 day of April, 19 58

Rose Furey
Notary Public.

My commission expires Feb. 13, 1960

PLUGGING
FIL SEC 24 T. 9 R. 24
BOOK PAGE 91 LINE 20

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY H-30, Inc.

SEC. 24 T. 9 R. 24
LOC. SE SE SE 1/4

FARM Lickelson

NO. 1

COUNTY Franklin

TOTAL DEPTH 4074


COMM. 3/19/58

COMP. 3/30/58

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED



CASING

20	10
15	8 197'
12	6
13	5

2489 KB
2486 LF
ELEVATION 2484 GF

PRODUCTION J . A

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	10'
Clay & sand	65
Shale	197
Shale & shells	400
Shale & shells with shallow sand stks	1200
Shale & shells with sand stks	1660
Sand	1870
Shale & shells	2121
Anhydrite	2165
Shale & shells	2545
Shale with lime stks	2550
Shale & lime	3850
Kansas City Lime	4074

Formation Tops:

Heebner	3795'
Toronto	3819'
Lansing K.C.	3836'
Base K. C.	4057'
T. D.	4074'

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

[Signature]

STATE OF KANSAS

COUNTY OF SEDGWICK

SS,

Subscribed and sworn to before me, a notary public, in and for said County and State this 4th day of April, 1958

[Signature]

My Commission Expires February 13, 1960