

KANSAS

Form CP-3
Rev. 6-26-62STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name Nickelson Well No. 4-W

Location CSW-NE Sec. 15 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4048'

Abandoned Oil Well ☒ Gas Well ☒ Input Well ☒ SWD Well ☐ D & A ☐

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company, Incorporated,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 11:30 AM Day 24 Month 6 Year 1969

The Above well was plugged as follows:

220'--8 5/8" Surface casing, cement circulated.4048'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3940'. Top perforations @ 3863. Hole in 5 1/2" casing @ 1160'. Chem-Pack had been staged around 5 1/2", had entered thru hole @ 1160' and stood inside 5 1/2" @ 275'.Ran 2" tubing to bottom and displaced 35 Sx. cement thru tubing. Allowed cement to set then squeezed 5 1/2" thru hole @ 1160' with 100 Sx. cement pumping plug to 1125' with clear water. (No pressure encountered). Attempted to squeeze well---pumped in 5 sacks hulls, followed with 10 sacks gel then 5 sacks cement. Encountered 1000# pressure which remained constant when well was closed in. (Mudding and cementing by Halliburton).

RECEIVED

I hereby certify that the above information is true and correct as herein stated.

JUL 1 1969

CONSERVATION DIVISION
Wichita, KansasSigned: M. L. Nichols

Well Plugging Supervisor

DATE 7-1-69INV. NO. 26-W