

KANSAS

Y STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 26 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin-Kantor & Executive,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Nickelson Well No. C-2

Location SE-NW-SE Sec. 14 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 3975'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kans. License No.

Operation Completed: Hour 2:00 PM Day 23 Month 7 Year 1971

The above well was plugged as follows:

172'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru
DP from 1175' to 850'. Pulled DP to 185' and displaced 20 Sx. cement thru DP from
185' to 125'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INDEXED
DATE 7-29-71
INV. NO. 4058-W

Signed: M. L. Deibel
Well Plugging Supervisor