



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
2-7-74  
FEB 7 3 54  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name F. C. H. Oil Company,

Complete Address 603 Union Center Building, Wichita, Kansas.

Lease Name Nickelson Well No. 1

Location SE-SE-NW Sec. 11 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4000'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Rockhold Engineering, Incorporated,

Address Box #698, Great Bend, Kansas. License No. 670

Operation Completed: Hour 1:30 PM Day 4 Month 2 Year 1974

The above well was plugged as follows:

185'--8 5/8" Surface casing, cement circulated.  
3999'--5 7/8" Production casing cemented on bottom with 100 Sx. Top of cement 3430'. No plug-back indicated, top perforations from 3842' to 3845'.  
Pushed plug to 3800', sanded well back to 3750' and set 5 Sx. cement with dump bailer.  
Pulled 5 7/8" casing (1138') and squeezed well initially with 5 sacks hulls and 15 sacks gel and followed with 110 Cu. Ft. cement from 1225' to 900' then 17 sacks gel from 900' to 220' and followed with 30 Cu. Ft. cement from 220' to 145' then 3 sacks gel from 145' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure-400%. FSIP-200%. (Mudding & cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Dinkel  
Well Plugging Supervisor

2/8/74  
8533-W