

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION

5-11-64
MAY 11 1964

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Vaughan Drilling, Incorporated.

Complete Address: 1314 Kansas, Great Bend, Kansas.

Lease Name Nickelson Well No. 1

Location CSW-SE Sec. 14 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 3980

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 2:30PM Day 7 Month 4 Year 1964

The Above well was plugged as follows:

187'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 180', set plug with 1/2 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols
Well Plugging Supervisor

DATE 5/12/64
INV. NO. 918-W