

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don E. Pratt,
Complete Address: Drawer #370, Hays, Kansas.
Lease Name Nickelson Well No. 1
Location SW-NE-SW Sec. 11 Twp. 9 Rge. (E) (W) 24
County Graham Total Depth 4045'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Knight Casing Pulling Company, Incorporated,
Address: Box #405, Chase, Kansas. License No. 436
Operation Completed: Hour 11:30 AM Day 3 Month 10 Year 1968

The Above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated.
4044'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 4015'. Top perforations from 3988' to 3991. Top of Dakota section @ 825'.
Sanded well back to 3950' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well with 15 sacks gel with 5 sacks hulls in initial gel and followed with 100 Sx. cement from 1050' to 725', then 12 sacks gel from 725' to 225' and followed with 20 Sx. cement from 225' to 165' then 3 sacks gel from 165' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--200#. Final shut-in pressure 100#. (Cementing & Mudding operations performed by Globe Cementing Company).

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION
10-7-68
OCT 7 - 1968
CONSERVATION DIVISION
Wichita, Kansas

Signed: M. L. J. J. J. J.

Well Plugging Supervisor

INVOICED

DATE

10/7/68

INV. NO.

8579-W