

KANSAS

*W* STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

8-4-66  
RSC 4

Operator's Full Name Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name Nickelson A <sup>RT</sup> KCC Well No. A-4

Location SE-NW-SW Sec. 23 Twp. 9 Rgo. 9 24

County Graham Total Depth 4060

Abandoned Oil Well Gas Well Input Well SWD Well D & S X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 11:45 AM Day 1 Month 8 Year 1966

The Above well was plugged as follows:

204'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 210', set plug with 1/2 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Dechels*  
Well Plugging Supervisor

DATE 8/4/66  
WELL NO. 3693-U