

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 47-12

LOCATION SW SW NW

SEC 23 TWP. 9 RGE. 24w

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Nickelson

Operator Empire Drg Co Address Wichita, Kans

Field \_\_\_\_\_ County Graham

Total Depth ~~3330~~ <sup>15</sup> 4060 <sup>21</sup> feet

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 180' circulated with cement. 5 1/2" at 4060' with

75 sax cement behind - P.B. to 3950', perforated at 3833'

Filled with sand to 3810', set 4 sax cement with dump bailer,

pulled 2840' 5 1/2" - filled with mud to 180', set rock and 15

sax cement, mud to 35', set rock and 10 sax cement to bottom

cellar.

District Conservation Agent

4-26-56

Date \_\_\_\_\_

REMOVED  
4-30-56  
APR 30 1956

CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 23 T 9 R 24w  
BOOK PAGE 47 LINE 12