

76
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

1-24-66
JAN 24 1966
RECEIVED
CONSERVATION DIVISION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Eben Drilling, Incorporated, et. al.,

Complete Address: 315 Wichita Plaza, Wichita, Kansas.

Lease Name Nickelson Well No. A-1

Location SE-SE-SW Sec. 23 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4060

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 11:00AM Day 20 Month 1 Year 1966

The Above well was plugged as follows:

215'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulated hole with heavy mud, set plug 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 210', set plug with 1/2 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of collar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Nichols*
Well Plugging Supervisor

1/24/66
2639-W