



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
11-25-74
NOV 25 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Nickelson 'A' Well No. 1

Location SE-SE-SW Sec. 23 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4060'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 2:30 PM Day 16 Month 11 Year 1974

The above well was plugged as follows:

215'--8 5/8" Surface casing, cement circulated with 150 Sx.
4060'--4 1/2" Production casing cemented on bottom with 125 Sx. Top of cement @ 3500'
(Temp. Survey). Top of perforations @ 3848'.

Push plug to 3600', sand back to 3550' and set 4 Sx. cement with dump bailer. Pulled
4 1/2" casing (1700') and squeezed well initially with 5 sacks hulls and 16 sacks gel
following with 110 Cu. Ft. cement from 1175' to 850' then 15 sacks gel from 850' to
250' and followed with 30 Cu. Ft. cement from 250' to 175' then 4 sacks gel from 175'
to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in
pressure-200%. FSIP-75%. (Mudding & cementing by Sun Oil Well Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickole
Well Plugging Supervisor

INVOICED

DATE 11/25/74
INV. NO. 356-W