

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

STATE CORPORATION COMMISSION
JAN 7 1971
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Woodman-Iannitti Oil Company,

Complete Address 706 Union National Building, Wichita, Kansas.

Lease Name Nickelson Well No. A-1

Location NW-NW-SE Sec. 24 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4020'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sun Oil Well Cementing, Incorporated,

Address Box #69, Hays, Kansas. License No. _____

Operation Completed: Hour 7:00 PM Day 26 Month 12 Year 1970

The above well was plugged as follows:

185'--8 5/8" Surface casing, cement circulated with 140 Sx.
4020'-5 1/2" Production casing cemented on bottom with 75 Sx. Well plugged back to
4004'. Top perforations from 3833' to 3837'.

Squeezed 5 1/2" casing initially with 1 sack hulls and followed with 25 Sx. cement then
28 sacks gel from 3700' to 950' and followed with 50 Sx. cement from 950' to 550'
then 3 sacks gel from 550' to 250' and finally 30 Sx. cement from 250' to bottom of
cellar. Squeezed annulus initially with 4 sacks then 7 sacks gel and finally 35 Sx.
cement.

I hereby certify that the above well was plugged as herein stated.

Signed: M. S. Nichols
Well Plugging Supervisor

1/7/71
3175-W