

KANSAS

*AL* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
1-6-71  
JAN 6 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Woodman-Iannitti Oil Company,  
Complete Address 706 Union National Bank Building, Wichita, Kansas.  
Lease Name Nickelson Well No. A-2  
Location CW/2-W/2-SE Sec. 24 Twp. 9 Rge. (E) (W) 24  
County Graham Total Depth 4020'  
Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Santa Fe Pipe and Supply, Incorporated,  
Address Box #562, Great Bend, Kansas. License No. 574  
Operation Completed: Hour 9:30 PM Day 26 Month 12 Year 1970

The above well was plugged as follows:

185'--8 5/8" Surface casing, cement circulated with 140 Sx.  
4017'--5 1/2" Production casing cemented on bottom with 75 Sx. Well plugged back to 4001'.  
Top perforations @ 3888'.

Pushed plug to 3825', sanded back to 3800' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 18 sacks gel and followed with 115 Sx. cement ~~then~~ from 950' to 575' then 9 sacks gel from 575' to 225' and followed with 25 Sx. cement from 225' to 150' then 3 sacks gel from 150' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure-- 150#. Final shut-in pressure-50#. (Mudding and cementing by Sun-Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichole*  
Well Plugging Supervisor

DATE 1-6-71  
WV. NO. 3158-W