

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION  
3-30-64  
MAR 30 1964  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Woodman-Iannitti Oil Company,  
Complete Address: 714 Union National Bldg., Wichita, Kansas.  
Lease Name #4 Nicholson Well No. A  
Location CN/2-SE Sec. 24 Twp. 9 Rge. (E) (W) 24  
County Graham Total Depth 4020  
Abandoned Oil Well Gas Well Input Well SWD Well D & A X  
Other well as hereafter indicated: \_\_\_\_\_  
Plugging Contractor: Woodman-Iannitti Drilling Company,  
Address: 714 Union National Bldg., Wichita, Kansas No.  
Operation Completed: Hour 1:00AM Day 25 Month 3 Year 1964

The Above well, was plugged as follows:

193'--8 5/8" Surface pipe, cement circulated with 130 Sx.  
Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.  
cement thru DP. Heavy mud to 180', set plug with  $\frac{1}{2}$  sack hulls and dis-  
placed 70 Sx. cement thru DP. Heavy mud to 35', set plug with  $\frac{1}{2}$  sack  
hulls and 10 Sx. cement to bottom of cellar.  
\_\_\_\_\_  
\_\_\_\_\_

I hereby certify that the above well was plugged as herein stated.

APPROVED  
DATE: 3/30/64  
BY: 8895-U

Signed: [Signature]  
Well Plugging Supervisor