

Attn: Richard

Amended

25 IE 3/45

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 033-20813 - 00 - 00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 02/28/1991

Well Operator: Pratt Well Service, Inc. KCC License #: 5893
(Owner / Company Name) (Operator's)

Address: PO Box 907 City: Pratt

State: Kansas Zip Code: 67124 Contact Phone: (620) 672 - 9571 Ext 5

Lease: Burkhall Well #: 2 Sec. 17 Twp. 31 S. R. 18 East West

NE - NW - SW Spot Location / QQQQ County: Comanche

2310 Feet (in exact footage) From ~~North~~ / South (from nearest outside section corner) Line of Section (Not Lease Line)

4290 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 638' Cemented with: 300 Sacks

Production Casing Size: 5 1/2" Set at: 5180' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs 4997' to 5000' retrievable bridge plug @ 5050'

4730 Tagged cement 25sks 100# Halls

Elevation: 2215 (G.L. / K.B.) T.D.: 5300 PBTD: _____ Anhydrite Depth: pipe recong 2885
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): sand back or set CIBP within 50' of perfs - cap with cement - pull casing

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? no well records 1050 15 50 660 50 40 20

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Gareld Inslee

Pratt Well Service, Inc. Phone: (620) 770 - 0995 (cell phone)

Address: P O Box 907 City / State: Pratt, KS 67124

Plugging Contractor: Quality Well Service KCC License #: 31925
(Company Name) (Contractor's)

Address: 190 US Hwy 56 Ellinwood, KS 67526 Phone: (620) 727 - 3409

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent.

Date: 11/17/08 Authorized Operator / Agent: Kent C. [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 09 2009

CONSERVATION DIVISION
WICHITA KS

KCC PLR

11

PT

Quality Well Service, Inc.

190 US Highway 56
Ellinwood, KS 67526

Invoice

Date	Invoice #
2/3/2009	1045

Bill To
Pratt Well Service, Inc. PO Box 847 Pratt KS 67124

P.O. No.	Terms	Lease Name
	net	Burkhall 2

Description	Qty	Rate	Amount
Rig Time	34	190.00	6,460.00T
Floor Rental		125.00	125.00T
Shots	2	300.00	600.00T
Torch		50.00	50.00T
Water Truck	3	85.00	255.00T
Backhoe	3.5	85.00	297.50T
Out of Town	2	120.00	240.00T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
Wiping Rubber		20.00	20.00T
Subtotal			8,082.50
7% Fuel Surcharge		7.00%	565.78T
<p>1-22-09 Drove to location, unhooked well head, raised pole, changed over for rods, pulled rods, changed over for tubing, pulled tubing, drove in.</p> <p>1-23-09 Drove to location, dug cellar, unpacked casing head, set floor, rigged up floor, hooked up to 5 1/2" casing, pumped 25 sacks, 100# hulls, displaced to 4730', max pressure 300, shut in 150 psi, drove in.</p> <p>1-27-09 Drove to location, tagged cement at 4730', pulled slips, had 24" stretch, cut surface off 4' below ground, ripped casing at 3050', worked pipe, ripped casing at 2885', pipe came free, pulled casing up to 1050', swedge in, drove in.</p>			
		Subtotal	
		Sales Tax (5.3%)	
		Total	

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 09 2009
CONSERVATION DIVISION
WICHITA, KS

Quality Well Service, Inc.

**190 US Highway 56
Ellinwood, KS 67526**

Invoice

Date	Invoice #
2/3/2009	1045

Bill To
Pratt Well Service, Inc. PO Box 847 Pratt KS 67124

P.O. No.	Terms	Lease Name
	net	Burkhal 2

Description	Qty	Rate	Amount
1-28-09 Drove to location, had to wait on water truck, pumped 15 gal, 50 sacks, 100# hulls at 1050', pulled to 660', pumped 50 sacks, 100# hulls, pulled to 40', pumped 20 sacks to surface, tore down floor and rig, emptied water out of cellar, cleaned up location.			
Subtotal			\$8,648.28
Sales Tax (5.3%)			\$458.36
Total			\$9,106.64

RECEIVED
 KANSAS CORPORATION COMMISSION
 FEB 09 2009
 CONSERVATION DIVISION
 WICHITA, KS