

15-065-20720-0000



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-21-74
OCT 21 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Barnett Oil, Incorporated,

Complete Address 411 First National Bank Building, Wichita, Kansas.

Lease Name Schweitzer Well No. 1

Location NE-SE-SE Sec. 35 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3975' ^{RT} _{KCC}

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 12:00 M Day 17 Month 10 Year 1974

The above well was plugged as follows:

^{16 RT KCC}
230'-- 8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 110 Cu. Ft. cement thru DP from 1100' to 775'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/23/74

INV. NO. 101-W