

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION CNE NE

SEC. 4 TWP. 9 RGE. 24

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. E-2 Lease Keith "E"

Operator Herman George Kaiser Address 909 Palace Bldg Tulsa, Okla

Field _____ County Graham

Total Depth 4065 Feet.

Plugging Contractor Ace Pipe Pulling

Plugging Contractor's License No. 2

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 190' circulated with cement - 5 1/2" 4065' with 125 sax
cement behind - P. B. 4000', perforations 3954'

Sand to 3940', set 4 sax cement with dump bailer, pulled 3100' 5 1/2",
stopped 5 1/2" at 700', circulated hole with heavy mud, spotted 40 sax
cement through 5 1/2" at 700', heavy mud to 40', set rock and 10
sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

District Conservation Agent

Date 6-2-57

6-7-57

PLUGGING
FILE SEC. 4 T. 9 24W
BOOK PAGE 18 LINE 19

CP-3