

15-065-02833-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
8-20-65
AUG 20 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Fender Pipe and Supply, Incorporated,

Complete Address: Box #302, Russell, Kansas.

Lease Name Hildebrand Well No. 1

Location CN/2-NW-SW Sec. 4 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4050

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Barnes and Sons Pipe Pulling Company,

Address: 1450 Maple, Russell, Kansas. License No. 9

Operation Completed: Hour 12:30PM Day 19 Month 8 Year 1965

The Above well was plugged as follows:

235'--8 5/8" Surface casing cement circulated. (No amount indicated)

4048'--5 1/2" Production casing cemented with no amount indicated.

Well plugged back to 4013' with top perforations from 3979' to 3984'.

Sanded well back to 3970' and set 5 Sx. cement with dump bailer. Water level in hole high, elected to squeeze through surface pipe with 35 Sx. gel and follow with 75 S. cement. Started to squeeze, pumped in 35 Sx. gel and gained circulation around surface pipe with no indicated pressure. Shut down overnight. Ran 600' 2" tubing and displaced 30 Sx. cement thru tubing. Pulled tubing to 270' and displaced 100 Sx. cement thru tubing which brought cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Daniels*
Well Plugging Supervisor

DATE 8/20/65

INV. NO. 1665-W