

15-065-03118-0001<sub>2</sub>

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
2-27-74  
FEB 27 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Petroleum Management, Incorporated,

Complete Address 1515 KSB&T Building, Wichita, Kansas.

Lease Name Holly Unit Well No. 16-2

Location NE-NE-NW<sup>SW</sup> Sec. 5 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4035'

Abandoned Oil Well        Gas Well        Input Well X SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Halliburton Services,

Address Drawer "D", Hill City, Kansas. License No.       

Operation Completed: Hour 2:00 PM Day 20<sup>1 RT</sup> Month 2 Year 1974

The above well was plugged as follows:

232'--8 5/8" Surface casing, cement circulated.  
4021'--4 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3985'. Top perforations from 3956' to 3962'.  
Sanded well back to 3930' and set 3 Sx, cement with dump bailer. Pulled 4 1/2" casing (2621') and squeezed well initially with 5 sacks hulls and 18 sacks gel and followed with 110 Cu. Ft. cement from 1125' to 800' then 13 sacks gel from 800' to 280' and followed with 30 Cu. Ft. cement from 280' to 200' then 4 sacks gel from 200' to 40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure-400#. Final shut-in pressure-150#.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Dinkel  
Well Plugging Supervisor

INVOICED

DATE 2/27/74  
INV. NO. 8655-40