

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2-27-74
FEB 27 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Petroleum Management, Incorporated,

Complete Address 1515 KSB&T Building, Wichita, Kansas,

Lease Name Holly Unit Well No. 17-2

Location CNW-SE Sec. 5 Twp. 9 Rge. (E) (W) 2b

County Graham Total Depth 4060'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Halliburton Services,

Address Drawer "D", Hill City, Kansas, License No.

Operation Completed: Hour 11:30 AM Day 21 Month 2 Year 1974

The above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated with 160 Sx.

4060'--4 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 4028'. Top perforations from 3982' to 3988'.

Sanded well back to 3960' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing (1256') and squeezed well initially with 5 sacks hulls and 18 sacks gell and followed with 110 Cu. Ft. cement from 1125' to 800' then 13 sacks gel from 800' to 280' and followed with 30 Cu. Ft. cement from 280' to 200' then 4 sacks gel from 200' to 40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure 450#. Final shut-in pressure-150#.

I hereby certify that the above well was plugged as herein stated.

Signed: R. L. D. [Signature]
Well Plugging Supervisor

INVOICED
DATE 2/27/74
INV. NO. 8657-40