

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
2-27-74
FEB 27 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management, Incorporated.
Complete Address 1515 KSB&T Building, Wichita, Kansas.
Lease Name Holly Unit Well No. 17-1
Location NE-NE-SE Sec. 5 Twp. 9 Rge. (E) (W) 2h
County Graham Total Depth 4070'
Abandoned Oil Well Gas Well Input Well X SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Halliburton Services.
Address Drawer "D", Hill City, Kansas. License No.
Operation Completed: Hour 1:30 PM Day 21 Month 2 Year 1974

The above well was plugged as follows:

232'--8 5/8" Surface casing, cement circulated.
4069'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to
4024'. Top perforations from 3987' to 4012'. 5 1/2" casing has been squeezed @ 1355'
with 100 Sx. cement.

Banded well back to 3960' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(1158') and squeezed well initially with 5 sacks hulls and 18 sacks gel and followed
with 110 Cu. Ft. cement from 1125' to 800' then 13 sacks gel from 800' to 280' and
followed with 30 Cu. Ft. cement from 280' to 200' then 4 sacks gel from 200' to 40'
and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in press-
ure-150#. Final shut-in pressure-50#.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 2/27/74

INV. NO. 8656-W