

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
4-10-72
APR 10 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,

Complete Address Box #922, Great Bend, Kansas.

Lease Name Robert McKinley Well No. 2

Location SE-NW-NE Sec. 6 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 3956'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 4:00 PM Day 5 Month 4 Year 1972

The above well was plugged as follows:

310'--10 3/4" Surface casing, cement circulated with 210 Sx.
3951'--7" OD Production casing cemented on bottom with 100 Sx. DV Tool set @ 2188'
with 150 Bbl. Chem-Pak. Well plugged back to 3946'. Top of perforations @ 3917'.

Sanded well back to 3890' and set 5 Sx. cement with dump bailer. Pulled 7" OD casing
(1256') and squeezed well initially with 7 sacks hulls and 16 sacks gel and followed
with 145 Cu. Ft. cement from 1200' to 875' then 14 sacks gel from 875' to 350' and
followed with 35 Cu. Ft. cement from 350' to 270' then 10 sacks gel from 270' to 30'
and finally 20 Cu. Ft. cement from 30' to bottom of cellar. Maximum pump-in pressure
-450#. Final shut-in pressure-250#. (Mudding and cementing by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 4-11-72

INV. NO. 5525-W