

15-065-02662-0001

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
4-10-72
APR 10 1972
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management, Incorporated,
Complete Address Box #922, Great Bend, Kansas.
Lease Name Robert McKinley Well No. 5
Location NW-SE-NE Sec. 6 Twp. 9 Rge. (E) (W) 24
County Graham Total Depth 3969'
Abandoned Oil Well Gas Well Input Well X SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling, Incorporated,
Address Box #364, Great Bend, Kansas. License No. 399
Operation Completed: Hour 6:15 PM Day 5 Month 4 Year 1972

The above well was plugged as follows:

320'-- 9 5/8" Surface casing, cement circulated with 325 Sx.
3969'--5 1/2" casing cemented on bottom with 100 Sx. Well plugged back to 3931'. Top
of perforations @ 3783'. DV Tool set @ 2157' with 125 Bbl. Chem-Pak. Junk in hole
@ 3250'.
Pushed plug to top of junk @ 3250', sanded well back to 3225' and set 5 Sx. cement
with dump bailer. Pulled 5 1/2" casing (1498') and squeezed well initially with 7 sacks
hulls and 16 sacks gel and followed with 145 Cu. Ft. cement from 1200' to 875' then
14 sacks gel from 875' to 350' and followed with 35 Cu. Ft. cement from 350' to 275'
then 10 Sx. gel from 275' to 30' and finally 20 Cu. Ft. cement from 30' to bottom of
cellar. Maximum pump-in pressure-350#. Final shut-in pressure-200#. (By Halliburton).
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols
Well Plugging Supervisor

DATE 4-11-72INV. NO. 5528-02