

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
4-10-72
APR 10 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management, Incorporated,

Complete Address Box #922, Great Bend, Kansas.

Lease Name Robert McKinley Well No. 11

Location SE-NE-NE Sec. 6 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 3956'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 10:45 AM Day 5 Month 4 Year 1972

The above well was plugged as follows:

900'--8 5/8" Surface casing, cement circulated with 510 Sx.
3948'--5 1/2" Production casing cemented on bottom with 100 Sx. Top perforations from
3873' to 3875'. DV Tool set @ 2171' with 8 Bbl. Chem-Pak.

Pushed plug to 3850', sanded well back to 3825' and set 5 Sx. cement with dump bailer.
Pulled 5 1/2" casing (2995') and squeezed well initially with 5 sacks hulls and 9 sacks gel
and followed with 110 Cu. Ft. cement from 1200' to 875' then 21 sacks gel from 875' to
35' and finally 10 Cu. Ft. cement from 35) to bottom of cellar. Maximum pump-in press-
ure--600#. Final Shut-in pressure--250#. (Mudding and cementing by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Pichler*
Well Plugging Supervisor

DATE 4-11-72

INV. NO. 5527-W