

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
4-10-77
APR 10 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management, Incorporated,
 Complete Address Box #922, Great Bend, Kansas.
 Lease Name Robert McKinley Well No. 3
 Location NW-NE-NE Sec. 6 Twp. 9 Rge. (E) (W) 24
 County Graham Total Depth 3938'
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated
 Plugging Contractor Southwest Casing Pulling Company, Incorporated,
 Address Box #364, Great Bend, Kansas. License No. 399
 Operation Completed: Hour 1:00 PM Day 5 Month 4 Year 1972

The above well was plugged as follows:

^{10" RT}
~~318'~~ ²¹ ~~5/8"~~ Surface casing, cement circulated with 310 Sx.
 3930'--7" OD Production casing cemented on bottom with 100 Sx. Well plugged back to
 3786'. Packer, tubing and junk in hole from 2250' to TD.
 Pushed plug to top of junk @ 2250', sanded back from 2250' to 2225' and set 5 Sx.
 cement with dump bailer. Pulled 7" casing (1197') and squeezed well initially with
 7 sacks hulls and 16 sacks gel and followed with 145 Cu. Ft. cement from 1200' to
 875' then 14 sacks gel from 875' to 350' and followed with 35 Cu. Ft. cement from 350'
 to 270' then 10 sacks gel from 270' to 30' and finally 20 Cu. Ft. cement from 30' to
 bottom of cellar. Maximum pump-in pressure-500#. FSIP-300#. (By Halliburton)/.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. S. Pichels*
Well Plugging Supervisor

DATE 4-11-72
INV. NO. 5526-W