

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
1-20-72
JAN 20 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,

Complete Address Box #922, Great Bend, Kansas.

Lease Name Holly Unit-Tract #12 Well No. 2

Location NE-NE-NW Sec. 6 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 3978'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 1:00 PM Day 18 Month 1 Year 1972

The above well was plugged as follows:

180'--8 5/8" Surface casing, cement circulated with 100 Sx.
3972'--5 1/2" casing cemented on bottom with 75 Sx. No plug back indicated. Top of perforations @ 3812'.

Sanded well back to 3800' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (1115') and squeezed well initially with 5 sacks hulls and 10 sacks gel and followed with 110 Cu. Ft. cement from 1225' to 900' then 17 sacks gel from 900' to 220' and followed with 30 Cu. Ft. cement from 220' to 145' then 3 sacks gel from 145' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. (Mudding and cementing operations performed by Halliburton). Maximum pump-in pressure-400#. FSIP--300#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 1-20-72
INV. NO. 5042-W