

15-065-00848-0008

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
1-20-72  
JAN 20 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Petroleum Management, Incorporated,  
Complete Address Box #922, Great Bend, Kansas.  
Lease Name Holly Unit-Tract #12 Well No. 1  
Location NW-NW-NW Sec. 6 Twp. 9 Rge. (E) (W) 24  
County Graham Total Depth 4042'  
Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Southwest Casing Pulling, Incorporated,  
Address Box #364, Great Bend, Kansas. License No. 399  
Operation Completed: Hour 3:15 PM Day 18 Month 1 Year 1972

The above well was plugged as follows:

187'--8 5/8" Surface casing, cement circulated  
4036'--5 1/2" Production casing, cemented on bottom with 75 Sx. No plug back. Top perforations @ 3850'.  
Sanded well back to 3800' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (1208') and squeezed well initially with 5 sacks hulls and 9 sacks gel and followed with 110 Cu. Ft. cement from 1260' to 935' then 18 sacks gel from 935' to 215' and followed with 30 Cu. Ft. cement from 215' to 140' then 3 sacks gel from 140' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure -400#. Final shut-in pressure-200#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Dickel*  
Well Plugging Supervisor

INVOICED

1-20-72

5041-W