

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
6-26-67
JUN 26 1967
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Birmingham-Bartlett Drilling Company,

Complete Address: 300 Kaufman Building, Wichita, Kansas.

Lease Name Nickelson Well No. 2

Location SE-NW-SE Sec. 10 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4060'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe and Supply, Incorporated.

Address: Box #562, Great Bend, Kansas. License No. 574

Operation Completed: Hour 11:00AM Day 20 Month 6 Year 1967

The Above well was plugged as follows:

180'--8 5/8" Surface pipe, cement circulated.
4059'--5 1/2" Production casing cemented with 100 Sx. Well plugged back to
4010'. Top perforations @ 3997'.

Sanded well back to 3975' and set 5 Sx. cement with dump bailer. Pulled
5 1/2" casing and squeezed well with 35 sacks gel using 4 sacks hulls in
initial gel and followed with 75 Sx. cement. Maximum pump-in pressure
450#. Final shut-in pressure 50#. (Recovered 1464' 5 1/2" casing).

Mudding and cementing operations performed by Halliburton Co.)

I hereby certify that the above well was plugged as herein stated.

Signed: N. A. Nichols
Well Plugging Supervisor

INVOICED

DATE 6/26/67
INV. NO. 5449-W