

[Handwritten signature/initials]

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 65-35 6-35

LOCATION SE NE NW

SEC. 10 TWP. 9 RGE. 24

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 5 Lease IDA Keith

Operator N. C. R. A *21 KCL* Address 305 Rule Bldg Wichita, Kans

Field _____ County Graham

Total Depth 4008 Feet.

Plugging Contractor Ace Pipe Pulling

Plugging Contractor's License No. 2

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 224' circulated with cement - 5 1/2" at 4007' with 100

sax cement behind - cement to 3854' - perforated at 3812'

Filled with sand to 3800', set 4 sax cement with dump bailer,

pulled 1700' 5 1/2" - mud to 220', set rock and 15 sax cement,

mud to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 10 T 9 R 24
BOOK PAGE 6 LINE 35

[Stamp]
10-31-55
OCT 31 1955
CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent
Date 10-25-55